



ADDENDUM NO. 2

Palatka Kay Larkin Fire Station Bay Door and Window Wind Retrofit

Located at 500 N Moody Rd, Palatka, FL 32177

Monday, February 10, 2025

Architect of Record: Passero Associates, LLC
4730 Casa Cola Way, Suite 200
St. Augustine, FL 32095
(904) 224-7082

Christopher Nardone, AIA
cnardone@passero.com

PASSERO
architecture engineering

Passero Associates Project No. 20213160.0008

ADDENDUM NO. 2
Palatka Kay Larkin Fire Station Bay Door and Window Wind Retrofit
City of Palatka
Monday, February 10, 2025

The following items are clarifications, corrections, or additions to the contract documents. **THIS ADDENDUM TAKES PRECEDENCE OVER THE ORIGINAL PARTS OF THE CONTRACT DOCUMENTS.**

All the parts of the contract documents, not specifically modified by this or other addenda, remain in full force and effect.

Bidders shall thoroughly familiarize themselves with the contents of this Addendum before submitting bid proposals. **IT SHALL BE THE BIDDER'S RESPONSIBILITY TO INFORM THE SUBCONTRACTORS, SUPPLIERS, MANUFACTURERS AND OTHER PARTIES PARTICIPATING IN THE WORK OF APPLICABLE REQUIREMENTS IN THIS ADDENDUM.**

Bidders shall acknowledge receipt of this addendum, identified by number and date, on the Addenda Receipt form included in the Proposal Section of the Contract Documents and submitted as part of their Proposal. Failure to acknowledge receipt of Addendum may be grounds for rejection of the bid proposal.

Items amended to the Contract Documents are as follows:

BID FORMS

DRAWINGS – ARCHITECTURAL

DRAWINGS – STRUCTURAL

DRAWINGS – MEP

BIDDERS QUESTIONS AND ANSWERS

Q1: Are single phase or 3 phase power to be provided for the motors? Single phase does not require returning to the job and setting the limits on the operators.

A1: Provide single phase power to the motors per existing.

Q2: Do you want the PVC Windows with LOW E?

A2: Yes, provide Low E for PVC Windows.

Q3: Please provide the glass color for the windows.

A3: Clear glass; no tint.

Q4: What type of Locking Mechanism do you want for the Steel Door?

A4: Provide Schlage L9464 with XL11-886, including new threshold, weather striping and closer.

Q5: Do you want us to replace the blinds and window coverings? Or only remove and reinstall them after the windows replacement?

A5: Remove and reinstall existing blinds. Clean and protect during construction.

ADDENDUM NO. 2
Palatka Kay Larkin Fire Station Bay Door and Window Wind Retrofit
City of Palatka
Monday, February 10, 2025

Q6: Do we have to submit a project schedule before the award of the project?

A6: Per specification section 01 30 00 – ADMINISTRATIVE REQUIREMENTS and specification section 01 32 16 – CONSTRUCTION PROGRESS SCHEDULE, provide a construction progress schedule within 10 days after Notice to Proceed.

ADDITIONAL DOCUMENTS INCLUDED

END OF ADDENDUM NO. 2